

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


Company- RUDY HERMAN  
Farm- Richmond "A" No. 1

SEC. 15 T. 11 R.17W  
C W/2 NW SE

Total Depth. 3552'  
Comm. 2-28-61 Comp. 3-5-61  
Shot or Treated.  
Contractor.  
Issued. 8-26-61

County Ellis

KANSAS



Elevation. 1929' RB

Production. 30 BOPD

CASING:

8 5/8" 226' cem w/140 sx.  
5 1/2" 3528' cem w/100 sx. & 65 gals latex added.

Figures indicate Bottom of Formations.

COMPLETE DRILLERS LOG NOT AVAILABLE:

TOPS:

Anhydrite	1130
Topeka	2862
Heebner	3094
Toronto	3113
Lansing	3136
Conglomerate	3399
Simpson Shale	3426
Simpson Sand	3456
Arbuckle	3464

DST #1 3099-3180', op 1 hr w/a very weak blow & rec. 45' mud w/a few specks of oil. BHP 955#/20 min, FFP 75#/20 min.

DST #2 3190-3215', op 30 mins, w/a weak blow that died in 12 mins. Rec. 10' rotary mud, BHP 0#/10 min.

DST #3 3262-3350', op 1 hr & rec. 60' gas w/120' watery mud very slightly oil & gas cut. BHP 890#/20 min.

DST #4 3456-68' op 1 hr, rec. 60' gas & 135' slightly oil & gas cut mud. BHP 785#/20 min.

DST #5 3456-73', op 1 hr w/a strong blow thruout, rec. 180' gas & 430' heavy oil & gas cut mud. BHP 830#/20 min. IFP 80#, FFP 230#.

Total Depth 3552