

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bk Bldg., Wichita, Kansas.

Plotted

Plotted Texas CO.

THE NATIONAL REFG. CO.
Bemis No. 1.

SEC. 16 T. 11 R. 17W
SEC SW

Total Depth. 3443'
Comm. 6-11-36 Comp. 7-11-36
Shot or Treated. 1000 gals. acid.
Contractor.
Issued. 8-29-36

County. Ellis

AUG 29 1936



CASING:
15 1/4" 105'
10 " 1047'
7 " 3348'

Elevation.

Production. Dry

Figures Indicate Bottom of Formations.

sand	20
shale & shells	807
shale red	900
shale	1000
shale red	1039
anhydrite	1080
shale red	1170
shale & shells	1420
salt	1610
lime & shale	1800
broken lime & shale red	2130
shale & shells	2370
lime	2415
shale	2600
lime & shale	2720
shale	2780
lime	3020
shale	3040
SAMPLE LOG	
shale red & green	3050
shale	3060
lime	3305
conglomerate	3332
shale green	3338
lime	3345
shale green	3348
dolomitic lime	3352
red cherty conglomerate	3370
conglomerate	3403
sand & chert yellow	3443
Total Depth	

Cemented back to 3356. Acidized 1000 gals.
No results. Dry & Abnd.
Cored 3338-48 1/2'; 6' recovery.

Top Lansing 3060
Top Conglomerate 3305
Sh of oil 3120 Sh of wtr 3210
Trace oil 3348-52
Little water 3430-33