

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.  
412 Union National Bank Bldg, Wichita, Kansas.

*Plotted J.S.*

THE DICKEY OIL COMPANY.  
Carmichael "C" No. 4


SEC. 17 T. 11 R. 17W.  
CSL NW NW

Total Depth. 3361  
Comm. 5-26-41 Comp. 6-21-41  
Shot or Treated.  
Contractor.  
Issued. 8-23-41

County Ellis.

CASING.

15 $\frac{1}{2}$ " 35'  
10" 1096'  
7" 3352 $\frac{1}{2}$ '



Elevation.

Production. Pot. 3000 B.  
Max.

Figures Indicate Bottom of Formations.

sand and shale	35
shale & shells	400
water sand	475
shale & shells	512
iron	530
shale & iron	590
water sand	730
red bed	1078
anhydrite	1120
shale & shells	1460
salt and shale	1630
shale and shells	1788
broken lime	1850
shale	1898
shale and lime	1975
shale and shells	1990
lime	2086
broken lime	2200
shale & shells	2253
broken lime	2320
shale and shells	2800
oil smell 2970-82	
lime	3126
Strong oil smell 3139-46	
lime	3310
red bed	3330
conglomerate	3342
shale green	3352
sand	3354
Arbuckle lime	3361
Total Depth.	

Tops. -	Anhydrite	1078	
	Topeka	2800	
	K.C. lime	3126	
	Arbuckle	3352	Corr. D.F.