

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

*Plotted
Lm.*


CHAMPLIN REFINING CO.
Hadley "D" No. 6

SEC. 17 T. 11 R. 17W.
CSL NE SW
990' S NL 660'W EL SW $\frac{1}{4}$

Total Depth. 3440
Comm. 2-17-41 Comp. 3-2-41
Shot or Treated.
Contractor.
Issued. 6-7-41

County Ellis.

Rotary



CASING.

85/8" 1152'9" Cem.
4 $\frac{1}{2}$ " 3440' Cem.

Elevation.

Production. Pot. 12,875 B.
Echomotor

Figures Indicate Bottom of Formations.

sand and shale	150
shale	465
sand and shale	535
pyrites of iron	570
iron pyrites	583
shale	640
sand	795
red bed	915
shale and sand	
red bed	1142
anhydrite	1153
anhydrite	1173
red bed	1273
shale	1400
salt and shale	1750
shale	1980
shale and lime	2075
lime and shale	2615
shale and shells	2705
shale & lime brkn	2825
shale and limo	2925
limo	3375
red shale & dol.	3384
dol. and shale	3396
limo	3430
corod	3436
lime	3439
shale green	3440

Total Depth.

Top Arbuckle 3397

4 $\frac{1}{2}$ " casing was set on bottom at 3440 and thru the oil pay the casing was then perforated opposite the oil pay with 60 shots from Lane Wells Gun.