

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk Bldg., Wichita, Kansas


*Plot 9*

CHAMPLIN REFG.CO.  
Hadley "D" No. 9.

SEC.17 T.11 R.17W  
SE SW NW SE  
1020' S NL 550' E WL SE  $\frac{1}{4}$

Total Depth. 3393'  
Comm. 4-1-41 Comp. 4-13-41  
Shot or Treated.  
Contractor.  
Issued. 7-12-41 Rotary 3393

County. Ellis



CASING:  
8  $\frac{1}{4}$ " 1125' Cem.  
4  $\frac{1}{2}$ " 3381' Cem.

Elevation.

Production. Pot.8577 B.Echo.

Figures Indicate Bottom of Formations.

sand, red bed	140
sand & shale	500
pyrite, shale	558 ✓
shale	620
sand	770
red bed	820
red bed & shale	1110
anhydrite	1135
red bed & shells	1350
shale & shells	1515
shale	1680
lime & shale	1770
shale & shells	1890
shale & lime shells	2040
lime & shale	2480
shale	2860
shale & lime	2940
lime	3015
shale	3055
shale, lime	3100
lime	3165
lime & shale	3215
lime	3250
lime & shale	3285
shale	3295
shale & lime	3360
lime	3393
Total Depth.	

Top Arbuckle 3382