

Plotted - 7-0-13.


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

THE DICKEY OIL COMPANY.
Husted No. 6

SEC. 18 T. 11 R. 17W.
CS $\frac{1}{2}$ SW SW

Total Depth. 3380
Comm. 11-4-40 Comp. 12-12-40
Shot or Treated.
Contractor.
Issued. 2-8-41

County Ellis.



CASING.

15 $\frac{1}{2}$ " 38'
10" 1135'
7" 3357'

Elevation.

Production. Pot. 1663 B.

Figures Indicate Bottom of Formation

shale	27
sand	37
post rock	38
shale and shells	191
shale	410
shale and shells	515
iron	545 ✓
shale and shells	635
sand	675
red bed	1110
anhydrite	1150
shale and shells	1475
salt	1650
shale and shells	1870
broken lime	1920
lime	2020
broken lime	2250
shale and shells	2812
lime	2828
lime and shale	2870
broken lime	2903
lime	3152
show of oil 3115-3124	
show of oil 3172-3177	
show of oil 3253-3257	
lime	3330
red bed	3352
shale green and chert	3357
lime	3380

Total Depth.

Tops	Topeka	2812
	K.C. lime	3130
	Arbuckle	3357 DF