


*Plotted  
Jm.*

THE DICKEY OIL CO.  
 Kollman No. 2

SEC. 18 T. 11 R. 17W.  
 CS $\frac{1}{2}$  SW NE

Total Depth. 3370  
 Comm. 2-15-40 Comp. 3-11-40  
 Shot or Treated.  
 Contractor.  
 Issued. 4- 6-40

County Ellis.



CASING.

15 $\frac{1}{2}$ " 34'  
 10" 1116'  
 7" 3360'

Elevation.

Production. Pot. 17,370 B.

Figures Indicate Bottom of Formations.

surface	34
shale and shells	510
iron	540 ✓
shale and shells	650
sand	764
red bed	1110
anhydrite	1145
shale and shells	1375
shale	1450
salt	1660
shale and shells	1812
broken lime	1970
lime	2023
broken lime	2275
shale and shells	2365
broken lime	2428
shale and shells	2800
lime	3012
lime	3316
red bed	3326
conglomerate	3337
Simpson dolomite	3345
shale green	3359
lime	3370

Total Depth.

Top Topeka lime	2800
Top Kans. City lime	3012
Top Arbuckle	3360