

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company. *Champlin Refining Co.*
REFINING CO.
Farm. Peavoy D No. 2

SEC. 19 T. 11 R. 17
NW SW S.
530' fr W line & 990' fr S
line of Sec. 19.
County. Ellis

Total Depth. 3475'

Comm. 9-15-47


Comp. 10-18-47

Shot or Treated.

Contractor.

Issued. 12-20-47

KANSAS



CASING:

10-3/4" O.D. 160' Cem. 1/100 Sx.
5-1/2" O.D. 3475' Cem. 1/300 Sx.

Elevation. *1928 feet*

Production. 50 Bbls.

Figures indicate Bottom of Formations.

shale ~ lime shells	550
hard sand & pyrites	565
sand ~ shale	970
shale	1165
anhydrite	1200
sand & shale	1360
shale ~ shells	1715
lime & shale	2085
sand & shale	2195
lime & shal	2285
sand & shale	2405
shale ~ lime	3355
lime	3468
lime & shale	3475

Total Depth

TOPO:

Topeka	2900
Heebner shale	3130
Base Pennsylvanian	3425
Lansing	3177
Arbuckle	3429