


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company-CHAMPLIN OIL & REFINING CO.
Farm- Feavey "D" No. 3

SEC. 19 T. 11 R. 17W
NE SE SW

Total Depth. 3677'
Comm. 10-11-59 Comp. 10-26-59
Shot or Treated.
Contractor.
Issued. 1-2-60

County Ellis KANSAS



Elevation. 2077 DF

Production. Dry

Figures indicate Bottom of Formations.

shelf & post rock	70
shale & shells	830
sand	980
shale & shells	1290
red bed & shale	1328
Anhydrite	1365
shale & shells	1835
shale w/ lime stks.	1990
shale & lime	2105
lime & shale	3380
Kansas City Lime	3416
lime	3453
Kansas City Lime	3496
lime	3545
lime & shale	3578
Kansas City Lime	3610
conglomerate	3636
cherty lime & shale	3677
Total Depth	

TOPS:	SAMPLE	ELEC. LOG
Heebner	3273	3271
Toronto	3294	3292
Kansas City	3317	3316
Base Kan. City	3573	3576
Conglomerate	3590	3590

DST #1 3384-3416 Open 2 hrs.
Recovered one qt. free oil, 15'
salty oil specked mud. ISIP 1,000#
in 30 min. FSIP 918# in 60 min.
IFP 20# FFP 20%.

DST #2 3574-3610 Open 2 hrs.
Recovered 160' oil, 240' oil cut
mud, 30' heavy oil cut mud.
IFP 55#, FFP 205# IBFP 935#
FBHP 390# in 60 min.