


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- PATTON OIL CO. & MURFIN DRILLING CO.  
Farm- Peavey Unit No. 10

SEC. 19 T. 11 R. 17W  
Approx. SW SE NE

Total Depth. 3550'  
Date. 7-5-61 Comp. 7-14-61  
Casing Treated.  
Drill Contractor. Murfin Drlg. Co.  
Logged. 9-30-61.

County Ellis KANSAS



CASING:  
8 5/8" 1219' cem w/500 sx.

Elevation. 1963' KB

Production. Dry

Figures indicate Bottom of Formations.

shale - shells	495
sand	610
hard sand pyrite	715 ✓
sand	885
red bed, shale	1020
red bed	1207
Anhydrite	1241
shale - shells	1570
salt, shale	1755
shale & lime	2210
lime & shale	2520
shale & lime	2915
lime & shale	3015
lime	3165
lime & shale	3250
lime	3400
lime & shale	3500
lime-chert-shale	3550
Total Depth	

TOPS: ELECTRIC

Anhydrite	1207
Topeka	2911
Heebner	3144
Toronto	3168
Lansing-Kansas City	3188
Base Kansas City	3429
Conglomerate	3470

DST #1 3445-3500' op 1 hr, rec. 15' mud.  
IF 0#, FF 0#, BHP 0#/20 min.