

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas

Company- Murfin Drilling Company
 Farm- Peavey Unit No. 12

SEC. 19
 SE NE SE


T. 11

R. 17W

Total Depth. 3470'
 Comm. 10-10-62 Comp. 10-16-62
 Shot or Treated. No
 Contractor. Murfin Drilling Co.
 Issued. 4-6-63

County Ellis

KANSAS



Elevation. 1906 KB

Production. Dry

CASING:

8 5/8" 210' cem w/150 sx.

Figures Indicate Bottom of Formations.

shale	15
sand	35
shale	212
shale & shells	445
sand	550
hard sand & iron	570 ✓
red bed & shale	1151
Anhydrite	1188
shale-shells	1685
shale & lime	2110
lime & shale	2460
shale-lime	2902
lime-shale	3025
lime	3440
Conglomerate	3470 RTD
Total Depth	

TOPS: SAMPLE

Anhydrite	1151
Topeka	2863
Heebner	3099
Toronto	3119
Lansing/Kansas City	3143
Base/Kansas City	3386
Conglomerate	3420

DST#1 3385'-3450' op 45 min. rec. 15'
 mud. IF 39# FF 39# FBHP 76#/20 min.