


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- MURFIN DRILG. CO.
Farm- Hadley "D" No. 7

SEC. 20 T. 11 R. 17W
NE NW NW

Total Depth. 3558'
Comm. 11-14-58 Comp. 11-24-58
Shot or Treated.
Contractor. Murfin Drilg. Co.
Issued. 2-14-59

County Ellis
KANSAS



CASING:
8 5/8" 1195' cem w/525 sx.
5 1/2" 3545' cem w/100 sx.

Elevation. 1942' DF

Production. 25 BOPD

Figures indicate Bottom of Formations.

shale - shells	505
sand - shale	585
iron pyrite	630 ✓
hard sand - pyrite	680 ✓
sand	840
red bed - shale	1191
Anhydrite	1226
shale - shells	1550
salt - shale	1715
shale - lime shells	2000
lime - shale	3455
Arbuckle	3555
lime	3558
Total Depth	

TOPS: LOG

Topeka	2898
Heebner	3128
Toronto	3149
Lansing-Kansas City	3171
Base Kansas City	3408
Simpson	3439
Arbuckle	3457

12-8-58 Perf. 3504-10, Tested 3 BOPH.
No water, acidized w/750 gallons @ 750#.
Swab back full load, tested 60 BOPH.
1400' off bottom.

No DST's