

J.C. Jones


CITIES SERVICE OIL CO.
 Bemis No. 14.

SEC. 21 T. 11 R. 17W
 SW NW NE
 996.4'S 330'E of Cen.

Total Depth. 3382'
 Comm. 12-11-37 Comp. 1-9-38
 Shot or Treated.
 Contractor. J.E. Mabee
 Issued. 3-5-38

County. Ellis

MAY 5 1938



CASING:
 15 $\frac{1}{2}$ " 101'
 10 $\frac{3}{4}$ " 1096'
 7 " 3369'

Elevation.

Production. Pot. 2092 B.
 No wtr, Nat.

Figures Indicate Bottom of Formations.

surface	25
shale	103
shale & shells	370
shale, shells, & sand	755
shale & shells	1070
lime	1080
anhydrite	1110
anhydrite & shale	1197
shale & shells	1480
salt	1617
shale & shells	1741
lime & shale	2066
brkn lime	2139
lime & shale	2195
shale & shells	2300
lime & shale	2363
lime	2410
lime & shale	2455
shale	2541
shale & shells	2720
shale	2803
shale & shells	2852
lime	3078
lime & shale	3227
lime	3281
lime & shale	3334
shale	3369
sand & shale	3371
lime	3372
lime (corod)	3373
very sm sh oil	3373
SLM Corr. 3373-3371	
lime sh oil	3382
Total Depth.	

Top Siliceous 3369'
 Pen. 13'
 T.D. 3382'

Pay 3371-3373 Some pay 3378-3382
 Fillup: 2300' 1 hr.
 2700' 1 $\frac{1}{4}$ hrs.
 2750' 2 $\frac{1}{4}$ hrs.