

PLOTTED
G.E. James


PHILLIPS PETRO.
F. Bemis No. 3

SEC. 21 T. 11 R. 17W.
CNL S $\frac{1}{2}$ NE

Total Depth. 3389
Comm. 10-28-36 Comp. 11-26-36
Shot or Treated.
Contractor.
Issued. 2-13-37

County Ellis. Texas CO.
Plotted Texas CO.

FEB 13 1937



CASING.

16" 62'
10 3/4" 1074'
7" 3363'

Elevation.

Production. Pot. 356 B.O.
14 1/2 BW 24 Hr.

Figures Indicate Bottom of Formations.

shale and shells	62	lime hard	2888
shale and shells	400	lime	2922
sand and iron-	500 ✓	lime hard	2937
iron	540 ✓	lime	2958
shale and iron	590 ✓	shale	2980
sand	715	lime	3330
shale and shells	760	shale	3345
shale & red bed	860	lime & sand	3348
shale	990	lime	3352
red bed-lime	1050	sand and shale	3354
shale	1061	siliceous	3355
anhydrite	1075	SIM 3355 equals 3364	
anhydrite	1100	lime hard	3374
shale	1240	lime with scum oil	3379
shale and shells	1405	lime	3382 S.S.O.
shale	1430	lime hard	3385 1BOPH
salt	1630	lime	3387 4 BO 3 Hr.
lime	1740	3387 equals 3389 SLM	
shale	1775	Total Depth.	
lime	1970		
lime and shale	2115		
shale and lime	2205		
lime	2230		
sand	2250		
lime and shale	2290		
shale and shells	2350		
shale and lime	2445		
shale	2575		
lime hard	2604		
lime	2705		
lime and shale	2780		
lime hard	2797		
lime	2862		

350' oil in hole 19 hours with
1 BW bailed down to 250'
1/3 BW 6 hrs. filled up 500'