

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

Company- OKMAR OIL CO.

Farm- Hadley

No. 8

SEC. 21 T. 11

NE NW NW

R.17W

Total Depth. 3844'

Comm. 12-4-57

Comp. 12-18-57


Shot or Treated.

Contractor. Murfin Drlg. Co.

Issued. 5-10-58

County Ellis

KANSAS



Elevation. 1823' RB

Production. SWDW

CASING:

8 5/8" 1071' cem w/500 sx.

5 1/2" 3540' cem w/500 sx.

Figures Indicate Bottom of Formations.

sand & gravel	55
gravel & blue shale	85
shale - shells	445
sand - pyrite	485 ✓
iron - hard sand	575 ✓
sand	710
red bed - shale - shells	1060
Anhydrite	1095
shale - shells	1470
salt - shale	1647
shale - lime - shells	1840
lime - shale	3175
lime	3315
lime - shale	3365
Conglomerate	3486
chert - lime	3589
lime	3841
granite	3844 RTD
Total Depth	

TOPS:

Anhydrite	1060
Topeka	2798
Heebner	3033
Toronto	3056
Lansing-Kansas City	3081
Conglomerate	3347
Arbuckle	3486
Granite	3841