

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bk Bldg., Wichita, Kansas.

*Plotted
Albert J. H. H.*

MARGAY OIL CORP.
Bomis No. 1-C.

SEC. 22 T. 11 R. 17W
NW NE SW

15-051-05829

Total Depth. 3459'
Comm. 3-6-37 Comp. 4-7-37
Shot or Treated.
Contractor.

County. Ellis

Plotted Texas CO.

Issued. 5-8-37
CASING:
15 1/2" 99'
10 " 1159'
7 " 3445'

MAY 8 1937



Elevation.

Production. Pot. 2347 B.

Figures Indicate Bottom of Formations.

shale	99	brkn lime	2184
shells hrd & shale	158	sticky shale & shells	2217
shale & lime shells	299	conglomerate	2249
shale	330	lime	2283
iron pyrites	344	shale & shells	2312
shale & shells	443	red beds	2334
lime shells	450	shale & shells	2395
pyrites of iron	485	brkn lime	2498
sand	614	shale & shells	2723
pyrites of iron	632	lime	2745
sdv shale	635	brkn lime	2764
pyrites of iron	647	shale & shells	2892
sand & shale	658	lime	2979
pyrites of iron	663	shale	2993
brkn pyrites of iron	694	lime	3055
pyrites & lime	712	brkn lime	3070
pyrites	721	lime	3190
sdv shale	810	brkn lime	3230
brkn pyrites & lime	816	lime	3364
shale & shells	885	show oil 3325-3340	
red rock	898	brkn lime	3392
lime	905	lime	3403
red rock	930	brkn lime	3425
red rock & shale	973	shale green	3431
SLM Corr. 973-971		sand	3438
red beds	1122	lime	3445
red bed & pyrites	1147	shale green	3449
chalk	1152	lime hrd	3455
anhydrite	1159	lime	3459
anhydrite	1190	Total Depth.	
red beds & shale	1376		
shale & shells	1535		
salt	1620		
brkn lime	1680		
shale & shells	1790		
brkn lime	1819		
lime	1835		
brkn lime	1856		
lime	1898		
brkn lime	1961		
red rock	1973		
lime	2055		
sticky shale	2065		
shale & shells	2113		
sticky shale & lime	2151		
lime.	2171		