

*Plotted
Albert Wheeler*

MARGAY OIL CORP.
Bemis No. 20.

SEC. 22 T. 11 R. 17W
SW NE SW

Total Depth. 3489'
Comm. 4-11-37 Comp. 5-4-37
Shot or Treated.
Contractor.
Issued. 6-12-37

County. Ellis

CASING:
15 1/2" 58'
10 " 1195'
7 " 3489

JUN 12 1937



Elevation.

Production. Pot. 2383 B.

Figures Indicate Bottom of Formations.

cellar	10	sticky shale	2716
surface clay	20	shale	2740
shale & shells	58	lime	2788
shale	61	SLM Corr. 2788=2785	
shale & shells	85	shale & shells	2885
pyrites of iron	101✓	brkn lime	2910
shale & shells	323	lime	3118
shale	402	SLM Corr 3118=3132	
pyrites of iron	411✓	lime	3190
sticky shale	440	brkn lime	3252
sdv shale	485	lime	3439
shale & shells	502	brkn lime	3470
shale	529	conglomerate	3484
sand	608	coring	3489
shale & shells	681	Total Depth.	
iron pyrites	687✓		
shale	697		
shale & shells	706		
shale	717		
iron pyrites	724✓		
sticky shale	745		
sand	837		
shale red	854		
shale	890		
red bed	950		
red rock & shale	1106		
s hale red	1177		
shale red & shells	1186		
shale & shells	1190		
anhydrite	1195		
anhydrite	1223		
shale red	1349		
shale & shells	1573		
s alt	1708		
shale & shells	1785		
lime	1832		
shale & lime shells	1912		
shale	1955		
brkn lime	2108		
shale & lime	2284		
shale & shells	2315		
red bod	2345		
brkn lime	2521		
shale & shells	2699		