

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

BRITISH AMERICAN OIL PROD.CO.
F. A. Bemis No. 2


Sec 22 T. 11 R. 17W.
SW NW SW

Plotted Texas CO.

Total Depth. 3441
Comm. 12-22-36 Comp. 1-20-37
Shot or Treated.
Contractor.
Issued. 4-3-37

County Ellis.

APR 3 1937



CASING.

16" 145'
103/4" 1161'
7" 3435'

Elevation.

Production. Pot. 1560 B.

Figures Indicate Bottom of Formations.

shale and surface rock	144	lime hard	2230
lime hard and shells	165	broken lime	2260
lime hard	200	shale and shells	2350
shale and shells	350	lime	2355
sdv shale	390	shale	2365
shale and lime brown	440	broken lime	2380
hard iron ore	450 ✓	shale	2389
shale	460	shale	2400
shale and shells	512	broken lime & shale	2440
sand	570	brown shale	2467
shale shells & lime	685	broken lime	2472
shale hard & lime streaks	705	broken lime	2510
shale	725	shale and shells	2666
sand white clay	810	shale and shells	2745
shale	825	broken lime & shells	2765
lime hard	835	shale	2770
shale and shells	890	shale and shells	2800
shale	900	lime	2805
broken pyrites of iron	950 ✓	shale	2860
shale and lime	970	shale and shells	2895
shale and lime shells	1005	lime	2947
red bed shale and lime		sand	2955
shells	1060	lime	3015
shale and lime streaks	1098	lime hard	3127
shale lime streaks	1150	broken lime	3150
chalk	1158	shale and shells	3185
anhydrite	1162	shale and lime shells	3220
anhydrite	1200	lime	3254
red clay	1205	Top K.C. lime. 3240	
red sdv clay shells	1310	lime K.C.	3300
shale blue lime shells	1365	lime K.C.	3390
red bed and shells	1395	shale brown	3400
shale and lime shells	1530	conglomerate	3413
salt	1595	lime	3420
salt	1665	reamed 7 7/8 core hole to	
shale and shells	1705	9" 3420-	3425
broken lime	1750	shale	3427
shale and shells	1795	coring	3430
shale blue	1810	shale	3431
lime	1815	dolomite and sand	3433
shale blue	1830	sand and shale	3435
lime	1840	siliceous lime	3441
shale blue & red rock	1865	Total Depth	
broken lime	1890		
shale and shells	1920		
shale and lime	1975		
lime hard	1985		
shale and shells	2010		
lime	2035		
shale lime streaks	2055		
broken lime	2078		
lime	2095		
broken lime	2148		
lime	2160		
lime hard	2177		
broken lime	2185		