

Plotted
Robert H. K.

BRITISH AMERICAN OIL PROD. CO.
F. A. Bemis No. 4.

SEC. 22 T. 11 R. 17W
SWc SW

Total Depth. 3476
Comm. 2-5-37 Comp. 3-7-37
Shot or Treated.
Contractor.
Issued. 5-8-37

County. Ellis
Plotted Texas CO.

MAY 8 1937



Elevation.

CASING:

16"	142'
10 $\frac{3}{4}$ "	1200'
7"	3453'

Production. Pot. 2949 B.

Figures Indicate Bottom of Formations.

cellar	10	lime	3189
surface clay	25	brkn lime	3205
clay & shells	147	lime Kansas City	3445
shale	155	shale green	3450
shale & shells	280	lime	3463
shells	292	shale & lime	3466
pyrites of iron	300✓	Siliceous lime	3476
shale & boulders	435	Total Depth.	
sand	485		
shale & shells	570		
sand	615		
pyrites of iron	625✓		
shale & shells	765		
shale	840	First Potential 2949 Bbls.	
lime & shale	950		
pyrites of iron	960✓		
shale	985		
shale & Pyrites of iron	1000✓		
shale & shells	1130		
red bed & shells	1192		
chalk	1196		
anhydrite	1219		
red bed	1350		
shale	1400		
shale & red beds	1472		
shale & shells	1490		
salt	1740		
shale	1765		
lime & shale	1848		
shale & shells	1900		
lime	1920		
brkn lime	1960		
shale	2015		
lime	2041		
shale & shells	2058		
lime & shale	2120		
shale & shells	2160		
brkn lime	2175		
shale & shells	2230		
brkn lime	2315		
shale	2325		
brkn lime	2360		
shale & lime	2400		
brkn lime & shale	2440		
shale & shells	2476		
lime & shale	2542		
shale & shells	2715		
shale & lime	2735		
shale & shells	2830		
lime	2840		
shale & shells	2870		
shale & lime	2915		
brkn lime	2931		
lime Topeka	3095		
shale	3110		