

RYAN CONSOLIDATED PETRO. CORP.  
F.A. Bemis "A" No. 2

SEC. 22 T. 11 R. 17W.  
SWc NW NW


DEEPENING RECORD

Total Depth. 3475'  
Comm. 8-29-36 Comp. 11-4-36  
Shot or Treated.  
Contractor.  
Issued. 6-21-47

County Ellis.

CASING.

15 $\frac{1}{2}$ " 108'  
10" 1095'  
7" 3396'



Elevation. 1880

Pot. 2020 B.  
Production. Pot. 84 bbls.  
per hour pumping test.

Figures Indicate Bottom of Formations.

shale and shells	35
shale	140
sand and shale	388
shale and shells	550
iron	572 ✓
shale	576
shale and shells	980
shale and red bed	1089
anhydrite	1095
lime	1265
shale and lime	1324
shale and shells	1425
shale	1460
salt and sand	1701
lime and shale	1925
lime	2145
shale	2155
lime	2250
sand and lime	2300
shale	2430
lime	2460
shale	2490
shale and shells	2585
shale	2760
lime	2770
shale	2825
lime	3085
lime and shale	3150
lime	3360
shale	3384
Green Simpson shale	3392
Simpson sand	3398
siliceous lime	3403
Total Depth.	

DEEPENING RECORD:

T. D. - 3475  
I. P. - Pot. 40 B0 14 B7  
Comm. - 2- 5-47  
Comp. - 3-12-47

OID 3403  
lime 3403-3475  
Total Depth.