


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

RYAN CONSOLIDATED PETRO. CORP.
F.A. Bemis No. 7-A.

SEC. 22 T. 11 R. 17W.
CSL N $\frac{1}{2}$ NW

Total Depth. 3422. P.B. 3416
Comm. 7-7-40 Comp. 7-31-40
Shot or Treated.
Contractor. Big West Drilling Co.
Issued. 9-21-40

County Ellis.



CASING.

13 3/8" 104'
5 1/2" 3412'

Elevation.

Production. Pot. 2316 B.

Figures Indicate Bottom of Formations.

surface soil	100	shale and shells	2702
shale and sand	150	lime	2720
shale	310	shale	2730
sand and shale	573	lime	2743
shale and lime	588	lime and shale	2771
shale and sand	660	lime	2845
sand	770	shale and lime	2873
shale and sand	850	lime	2917
sand and iron	900	lime with strks of shale	2952
sand and shale	930	lime	3003
shale	1000	lime and chert	3030
shale iron and red bed	1116	lime	3360
anhydrite of lime	1125	shale	3398
anhydrite and iron	1160	dolomite & lime (coring)	3422
anhydrite	1180	Total Depth.	
shale	1325		
red bed and shale	1390	Plugged back to 3416	
shale	1480		
salt and anhydrite and shale	1676	shale	3398-3405
shale and anhydrite	1690	conglomerate	3405-3407
shale	1710	Frank Congl.	3407-3411 1/2
shale and lime	1828	Blk bituminous, shale, lime	
lime	1840	and iron pyrite	3411 1/2-3412
shale and lime	1955	cherty dol. lime	3412-3416 1/2
shale	1967	chert hard	3416 1/2-3417
lime	2018	dolomitic limestone	3417-3418
shale and shells	2040	Waxy green shale	3418-3418 1/2
sticky shale	2089	dolomitic lime-	
lime	2138	stone	3418 1/2-3422
shale and lime	2150	Oil (Arbuckle lime)	3412-3416
lime	2198		
shale and lime	2250		
lime	2275		
shale	2295		
lime	2335		
lime and shale	2391		
lime	2405		
sharp sand	2426		