


CITIES SERVICE OIL CO.
Jennie Johansen No. 2.

SEC. 22 T. 11 R. 17W
NE NW NE
330' S 990' E of N/4 Cor.

County. Ellis

Total Depth. 3449'
Comm. 7-25-37 Comp. 8-24-37
Shot or Treated. 2000 Gals.
Contractor. Twin Drlg. Co.
Issued. 11-20-37

NOV 20 1937



CASING:
16" 96'
10" 1135'
7" 3443'?

Elevation.

Production. Pot. 1900 B.

Figures Indicate Bottom of Formations. No wtr, after acid.

clay grey sticky	50	lime brkn med	2918
shale, shells blue med	490	lime lgt hrd	2965
sand red sft	590	lime lgt mod	2990
iron drk hrd	594	lime lgt hrd	3118
shale blue, lime shells		shale blue med	3140
sdy med	680	lime brkn lgt mod	3270
sand wh, iron shells	740	lime lgt hrd	3335
sand drk sft	800	sh oil 3310	
shale & sand grey med	850	lime lgt med	3398
shale & shells red med	1000	brkn limo mod & shale	
sdv shalo red sft	1135	red	3435
anhydrito limo	1142	varicolored shale	3440
anhydrito hrd	1174	shalo (cored)	3441½
shale red mod	1425	lime (cored)	3446
shale & shells blue mod	1495	SIM Corr. 3446 equals	3448
shale blue med	1510	lime	3449
salt & shalo mod	1530	Total Depth.	
salt lgt sft	1685		
shale blue med	1720		
shale blue & lime shells	1800	Top Conglomerate	3392
lime lgt hrd	1815	Top Simpson Dol.	3417
shale & shells blue	1844	Top Arbuckle	3444
lime grey hrd	1865	Pon.	5
shale & shells brown med	1879	T.D.	3449
shale brown med	1892		
lime lgt hrd	1902		
lime brkn lgt med	1925	Well tested 988 oil, no wtr.	
shale red sticky	1960	nat. 24 hrs.	
lime lgt hrd	1975		
shale blue & lime shells			
med	2094		
lime lgt hrd	2110		
lime brkn lgt med	2125		
lime lgt mod	2170		
lime lgt hrd	2255		
shale red med	2267		
lime lgt hrd	2285		
shale blue lime shell med	2305		
shale mod lime shells	2332		
shale & shells mod red	2340		
brkn lime	2440		
lime lgt mod	2460		
brkn lime mod	2558		
shale blue med	2585		
lime grey hrd	2591		
lime brkn mod	2641		
lime lgt brkn	2680		
lime lgt brkn mod blue			
shalo streak	2766		