

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.


J. E. Jameson

MARGAY OIL CO.
Johanson No. 1

SEC. 22 T. 11 R. 17W.
SW₆ SE

Total Depth. 3450
Comm. 6-2-37 Comp. 6-26-37
Shot or Treated.
Contractor.
Issued. 9-4-37

County Ellis.



CASING.

10" 1204
7" 3434'5"

Elevation.

Production. Pot. 2404 B.

Figures Indicate Bottom of Formations.

surface soil & clay	30	
clay	42	
shale and shells	562	
sand	620	
shale and shells	762	
sand	840	
sticky shale	938	
sticky red shale	1065	
shale and shells	1194	
chalk white	1196	
chalk	1199	
anhydrite	1204	
anhydrite	1225	
shale red and shells	1490	
shale and shells	1765	
broken lime	1820	
shale and shells	1935	
broken lime	2080	
lime	2103	
broken lime	2256	
shale and shells	2333	
shale	2348	
broken lime	2403	
lime	2430	
broken lime	2465	
sticky shale	2615	
shale and shells	2679	
sticky shale	2719	
sticky shale and shells	2791	
shale sticky	2867	
lime	3216	show of oil 3204-3212
lime	3298	
lime hard	3317	
lime	3430	
shale green	3433	
siliceous lime	3434'5"	
SLM corr. 3434'5 equals	3443	
lime	3450	

Total Depth.