

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bank Bldg, Wichita, Kansas.

*Plotted
J.M.*


CITIES SERVICE OIL CO.
Rumsey No. 10

SEC. 23 T. 11 R. 17W.
NE NW SE
330' S 990'E Con Soc.

Total Depth. 3418
Comm. 5-4-39 Comp. 6-23-39
Shot or Treated. 500 gal acid.
Contractor. J.E. Mabee Co.
Issued. 8-12-39

County Ellis.

CASING, Rotary 3412
Cable 3418



8 1/4" 1043'
5 1/2" 3414'

Elevation.

Production. Pot. 20,360 B.
Echo-Meter, 3500 B.
Maximum

Figures Indicate Bottom of Formations.

surface	73	Top Arbuckle	3413	Corr.
shale and shells	350	Penetration	5	
shale and sand	430			
shale and shells	670	FILLUP		
lime and shale	800	150' 30 Min.		
red bed	970	1800' 1 hour.		
shale and shells	976	2750' 2 hours.		
shale	1043			
shale and shells	1170	Pot. 20,360 B. Echo Meter.		
anhydrite	1205	Maximum 3500 B. After 500 gal acid.		
red bed	1243			
shale shells red bed				
and salt	1485			
salt and shale	1610			
shale and shells	1800			
lime	1822			
lime and shale	1900			
lime broken	2044			
lime and shale	2135			
lime broken	2155			
lime	2180			
lime broken	2195			
lime and shale	2360			
shale and shells	2848			
lime	2914			
lime broken	2943			
lime	3031			
lime broken	3177			
lime and shale	3234			
lime broken	3280			
lime	3398			
shale	3409			
lime broken	3412			
Top Arbuckle	3411			
T.D. rotary	3412 equals 3414 S.L.M.			
Top Arbuckle	3413	Corr.		
lime	3418			
Total Depth.				