

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.  
412 Union National Bank Bldg, Wichita, Kansas.


SHELL PETROLEUM CORP.  
J.L.Rumsey No. 3

SEC. 23 T. 11 R. 17W.  
NW SW NW  
990' SL 330' fr WL.

Total Depth. 3422.  
Comm. 1-12-38 Comp. 2-8-38  
Shot or Treated.  
Contractor. Twin Drlg Co.  
Issued. 3-19-38

County Ellis.

MAR 19 1938



CASING.

16" 208'  
10 3/4" 1118'  
7" 3398

Elevation.

Production. Pot. 2331 B.

Figures Indicate Bottom of Formations.

clay	45	lime	2560
shale and shells	270	lime broken	2620
sand	290	shale and lime	
shale and shells	355	shells	2680
shale red	391	lime	2695
shale and shells	485	shale and lime	
sand	589	shells	2725
iron	618	lime	2785
sand iron shells	627	shale & shells	2800
shale and shells	690	lime and shale	
red sand	700	breaks	2810
sand	777	shale	2823
shale	938	lime	2849
shale red	1000	shale	2855
shale and shells	1114	lime	2880
anhydrite	1128	shale and lime	
anhydrite and lime	1164	shells	2890
shale and shells	1200	lime	2958
shale	1300	lime	3114
shale and shells	1322	shale & lime shells	3131
shale and shells	1490	shale and lime	3144
shale and lime shells	1570	lime broken	3147
salt shale and shells	1692	lime	3203
shale and lime shells	1710	lime broken	3227
lime	1740	lime	3238
shale and lime shells	1762	shale & lime shells	3243
shale and lime shells	1779	lime	3260
chalk	1786	lime	3294
shale and lime shells	1800	lime & shale brks	3320
lime	1855	lime	3349
shale and lime shells	1905	lime & shale brks	3354
lime	1947	Conglomerate, shale	
shale	1960	red, lime, chert orange,	
lime	1970	reddish brown	3376
shale and lime shells	2005	dolomite bright	
lime broken	2030	green shale	3385
lime	2045	shale green and brown	
lime and shale breaks	2118	dolomite	3394
lime	2210	sand	3396
shale and lime shells	2265	small amount oil staining.	
lime and shale breaks	2275	shale green some	
lime	2290	brown	3398
shale	2300	dolomite	3399
shale and lime shells	2326	small amount oil staining.	
lime	2355	dolomite shale	3402
shale and lime shells	2395	small amount of oil	
lime	2410	3402 equals 3400 SLC (df)	
shale	2427	dolomite	3409
lime	2478	small amount oil	
shale	2485	dolomite	3422
lime	2495		
lime	2505	Total Depth.	
shale	2520		
shale and lime shells	2531		