

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY,
412 Union National Bank Bldg, Wichita, Kansas.


SHELL PETROLEUM CORP.
J.L. Runsey - No. 5

SEC. 23 T. 11 R. 17W.
SW SW NW
330' SL 330' WL.

Total Depth. 3388
Comm. 2-27-38 Comp. 3-28-38
Shot or Treated.
Contractor. Twin Drlg. Co.
Issued. 4-16-38

County Ellis.

APR 16 1938



CASING.

16" 197'
103/4" 1096'
7" 3374'

Elevation.

Production. Pot. 2642 B.

Figures Indicate Bottom of Formations.

shale and shells	300	shale and sholls	2660
shale and shells	350	limo	2700
shale	430	shalo	2721
shale and shells	465	limo	2729
sand	569	shalo	2731
iron	575 ✓	limo and shalo breaks	2762
sand and iron sholls	605 ✓	shalo	2788
shale and shells	633	limo	2793
shale and sholls	660	shalo	2804
sand	740	limo	2925
shale and shells	1094	Heavy Oil stain 2838-50	
anhydrite	1133	limo	3066
shale and sholls	1320	limo and shalo breaks	3079
shale and limo shells	1360	limo	3090
limo	1395	shale and sholls	3125
shale and limo shells	1450	limo	3145
shale and sholls	1560	limo and shalo breaks	3191
salt and shalo	1612	limo	3256
salt shalo and sholls	1640	limo and shalo breaks	3277
shale and sholls	1675	limo	3296
chalk	1691	limo and shalo breaks	3352
limo and shalo breaks	1745	shalo dolomito	3367
limo	1780	sand	3368
shalo	1792	shalo green & brown	3372
limo	1812	dolomito	3373 Oil stain
shalo and limo shells	1890	dolomito	3376
limo and shalo breaks	1905	3376 equals 3377 S.L.C.	
shale and sholls	1931	dolomito	3388
limo	1966		
shalo	1971	Total Dophth.	
limo	1993		
shalo	2005	Trace Oil stain 3070-75	
limo	2020	Trace Oil stain 3153-67	
shale and shells	2028		
shale and shells	2045	No. 1 Core 3373-76	
limo	2065	Fair amount of oil	
limo broken	2081		
limo	2120	No. 2 Core 3377-81	
shalo and limo breaks	2126	2900' oil	
limo	2210		
shale and shells	2255	No. 3 Coro 3381-86	
limo and shalo breaks	2269	Small amount of oil	
limo	2305		
limo broken	2318	No. 4 Coro 3386-88	
limo	2357	Porous oil stain.	
shalo	2368		
limo and shalo breaks	2380		
shalo and shells	2395		
limo	2441		
shale and shells	2462		
limo	2474		
shalo and sholls	2488		
limo	2510		
limo and shalo breaks	2525		
limo	2540		
limo broken	2562		
shalo and sholls	2610		
limo	2623		
limo and shalo breaks	2644		