


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
502 East Murdock, Wichita, Kansas

Company- CITIES SERVICE OIL CO.
Farm- Colahan "C" No. 9

SEC. 24 T. 11 R. 17W
CW/2 E/2 SE
1320' N. & 990' W. of SEC

Total Depth. 3432
Comm. 11-15-51 Comp. 11-26-51
Shot or Treated. 250 glas 12-6-51
Contractor. Lohmann-Johnson Drlg. Co., Inc.
Issued. 2-9-52

County Ellis KANSAS



Elevation. 1896
~~1892 (old)~~
Production. 86 BO 33 BW 24/hrs.

CASING:

9 5/8" 1093' cem. w/300 sx
7" 3428' cem. w/150 sx

Figures Indicate Bottom of Formations.

shale & shells	140
shale & sand	555
sand & shale	725
shale & shells	826
shale, sand & red bed	1078
anhydrite	1117
shells & shale	1345
shale & shells	1865
shale & lime	2030
lime & shale	2120
shale & lime	2406
lime & shale	2500
shale & shells	2695
shale & lime	2843
lime & shale	3228
lime	3432

3432 RTD = 3433 SLM
Total Depth

Tops; Corr.	
Heebner	3037
Dodge	3059
Lansing	3084
Arbuckle	3362

Penetration 71'
DST: 3427-32' open 30
mins. rec. 300' oil; 15
min. BHP 990#.

Fill Up:

100' oil in 30 mins.
290' oil " 1 1/2 hrs.
535' oil " 3 hrs 50 mins.
940' oil " 7 hrs.
1133' oil " 11 hrs.
1800' oil " 23 hrs.