


*Plotted
E.M.*

CITIES SERVICE OIL CO.
Colahan No. 1-B.

SEC.26 T.11 R.17W
SW NW NW
330'E 990'S NW Cor.

Total Depth. 3600'
Comm. 7-21-40 Comp. 8-24-40
Shot or Treated.
Contractor. Mabee O.G.Co.
Issued. 10-12-40

County. Ellis



CASING:
8 5/8" 1110' Cem.
5 1/2" 3555' Cem.

Elevation.

Production. Pot.2420 B.Echo.
No wtr

Figures Indicate Bottom of Formations.

shale & rock	70
shale	360
shale & sand	393
shale & shells	500
sand	560
shale & red bed	730
sand	830
shale & sand	950
shale & shells	1110
shale & red bed	1250
anhydrite	1280
lime	1290
red bed & shells	1450
shale & shells	1605
shale, salt, red bed	1685
shale & salt	1800
shale & shells	1900
shale & lime	2024
lime brkn	2130
shale	2185
lime	2202
lime brkn	2251
lime	2309
lime brkn	2328
shale & lime	2463
lime	2515
shale & lime	2838
shale & shells	2969
lime	3544
lime brkn	3555
lime cored (rec 3')	3558
rotary T.D. 3558-3559	SIM
lime	3559-3600
Total Depth.	

2000 Gals. 8-21-40
4000 Gals. 8-27-40
Corr. Top Arbuckle 3555
Penetration 45

Fillup: 150' oil in 1 hr @ 3562.
200' oil in 1 1/4 hrs @ 3562
1075' oil in 2 1/4 hrs @ 3566
2500' oil in 4 1/4 hrs
2575' oil in 5 1/4 hrs
2675' oil in 6 1/4 hrs

Jetted 500 Gals. Acid 8-21-40