


CITIES SERVICE OIL CO.
Colahan "B" No. 6.

SEC.25 T.11 R.17W
NEc NW
330'S 330'W of N $\frac{1}{4}$ Cor.

County. Ellis

Total Depth. 3429'
Comm. 7-2-41 Comp. 7-24-41
Shot or Treated.
Contractor. Mabee O.G.Co.
Issued. 9-6-41



CASING:
8 5/8" 1070' Cem.
5 1/2" 3405' Cem.

Elevation.

Production. Echo.Pot.16,751B.
No wtr

Figures Indicate Bottom of Formations.

shale & shells	535
sand	645
shale & shells	700
sand	765
shale & shells	840
shale & red bed	1070
red bed	1122
lime	1173
red bed, shale, shells	1440
red bed & shale	1500
salt	1650
shale & shells	1894
limo & shale	2541
shale & shells	2832
shale & limo	2892
lime	2923
lime & shale	3057
limo brkn	3114
limo	3220
lime brkn	3263
limo	3405
Arbuckle	3408
3408 Rot.TD=3408 SLM	
dolomite	3429
Total Depth.	

Top Arbuckle 3405
Penetration 24

7-20-41 1000 Gals.Acid
7-25-41 2000 Gals.Acid

Fillup:

600' oil in 50 min.
1050' oil in 1 hr 20 min
1350' oil in 2 hrs 20 min
1740' oil in 3 hrs 20 min
2300' oil in 7 hrs 20 min