

Plotted 95.


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.  
412 Union National Bank Bldg, Wichita, Kansas.

CITIES SERVICE OIL CO.  
Colahan "B" No. 7

SEC. 25 T. 11 R. 17W.  
SW NW SW  
950' So. 330' E. of W $\frac{1}{2}$  cor.

Total Depth. 3516  
Comm. 7-16-41 Comp. 8-5-41  
Shot or Treated. 2000 gal (8-6-41)  
Contractor. Mabee Oil and Gas Co.  
Issued. 9-27-41

County Ellis



CASING.

85/8" 348' cemented.  
5 1/2" 3479' cemented.

Elevation.

Production. Pot. 7658 B.

Figures Indicate Bottom of Formations. no wtr. Echometer.

shale and shells	585
sand and shale	660
iron shells and shale	750
sand and shale	758
shale shells and red bed	1100
shale and red bed	1160
anhydrite	1215
shale and shells	1275
shale, shells and red bed	1450
shale and shells	1550
salt and shale	1700
shale and shells	1812
broken lime	2075
2075 equals 2045 S.L.M.	
lime broken	2290
shale and lime	2335
sand and shale	2355
lime and shale	2638
shale and shells	2873
shale and lime	2927
lime	3182
lime broken	3197
3197 equals 3227 S.L.M.	
lime broken	3271
lime	3478
3478 Rotary T.D. equals	
3479 S.L.M.	
dolomite	3479- 3516

Corr. Top Arbuckle 3477  
Penetration 39'

FILLUP -

100'	oil in 1 1/2 hrs at 3489
250'	oil in 3 3/4 hrs at 3494
400'	oil in 6 1/2 hrs at 3499
1050'	oil in 10 1/2 hrs at 3504
2150'	oil in 11 hrs at 3504
2500'	oil in 12 hrs at 3504
2800'	oil in 14 hrs at 3504

Total Depth.