


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - CITIES SERVICE OIL COMPANY
Farm - Colahan "B" No. 17

SEC. 25 T. 11 R. 17W
NE SE NW
990' N & 330' W of Center

Total Depth. 3532' SIM PB 3521'
Comm. 2-2-47 Comp. 2-19-47
Shot or Treated. Acid. w/500 gals. 3-4-47
Contractor. Veeder Supply & Dev'l Co.
Issued. 5-17-47

County. Ellis
KANSAS



Elevation. 1971 *act*

Production. Phy. Pot: 80 BO,
1.5% B.S., 24 hrs

CASING:

8-5/8" 1084' Cem. w/500 sx
5-1/2" 3532' Cem. w/150 sx

Figures Indicate Bottom of Formations.

surface soil	0-40
shale	150
shale & shells	460
sand & shale	675
shale & shells	820
sand	890
shale & shells	970
pyrite	975
red bed	1074
shale	1137
red bed	1163
anhydrite	1198
shale & shells	1625
salt	1675
shale & shells	1795
lime & shale	1925
shale & shells	2020
lime & shale	2095
lime	2135
shale & shells	2190
lime & shale	2430
shale & shells	2795
lime & shale	2825
shale & shells	2970
lime & shale	3010
lime	3045
lime & shale	3080
lime	3536

3536 RTD= 3532 SIM

Total Depth 3532 SIM

Plugged back to 3521'

Tops:
Lansing 3204
Arbuckle Corr. 3451
Penetration 81

Drilled cement to 3521 SIM.

Perf. 54 shots 3507-17

50' fluid in 15 mins.
140' oil in 2 hrs. 20 mins.
215' oil in 4 $\frac{3}{4}$ hrs.
476' oil in 9 hrs. 10 mins.
1025' oil & $\frac{1}{2}$ bailer wtr, 19 hrs.