


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - CITIES SERVICE OIL COMPANY
Farm - Hall "B" No. 19

SEC. 26 T. 11 R. 17W
CN/2 SW SW
990' N & 660' E of SWc

Total Depth. 3512' SIM PB 3505'
Comm. 9-3-46 Comp. 9-20-46
Shot or Treated. Acidized
Contractor. Veeder Supply & Dev'l Co.
Issued. 1-11-47

County. Ellis
KANSAS



Elevation. 1956 *hd & set*

CASING:

8-5/8" 1070' Cem
5-1/2" 3512' Lem

Production. Phy. Pot: 88 oil,
no water, 24 hrs.

Figures Indicate Bottom of Formations.

surface soil	0-40
shale & shells	390
sand	460
shale & shells	720
sand & pyrite	830 ✓
red bed	845 ✓
sand, shale, pyrite	985 ✓
red bed	1065
blue shale	1070
shale	1125
red bed	1145
anhydrite	1190
red bed	1250
shale	1465
salt	1555
shale & shells	1760
sdv lime & shale	1830
shale & shells	1920
lime & shale	2310
lime brkn	2610
shale	2680
lime & shale	2790
shale & shells	2900
shale	2910
lime & shale	3215
lime	3280
lime & shale	3310
lime	3507

3507 Rot. TD=3512 SIM
Total Depth

Schlumberger log.
Gamma Ray-Neutron log.

Tops:
Arbuckle 3419
Penetration 93

Drilled cement to 3505 SIM.
1000 gals. 3436-61 (10-4-46)
1000 gals. 3415-31 (11-14-46)

Perf. 30 shots 3451-61
Perf. 24 shots 3436-44

1 bailer wtr & 1/4 bailer oil
every two hrs.

After 1000 acid, pumped 67 oil, 4% B.S.
& wtr, 24 hrs.

Perf. 71 shots 3415-31.