

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- Cities Service Oil Co.
Farm- Hall "B" No.24


SEC. 26 T. 11 R. 17W

(D.R.L. 10/64) NW NE SE NE SW

825' S
405' W of center
Ellis
KANSAS

County

Total Depth. 3556
Comm. 7-26-53 Comp. 8-19-53
Shot or Treated.
Contractor. Glenn R. Nye Drilling Co.
Issued. 10-10-53



Elevation. 2030 GR.

Production. 55 oil, 67 wtr in 24 hrs.

Figures indicate Bottom of Formations.

CASING:
8 5/8" 1230' cem. w/300 sx
5 1/2" 3552' cem. w/175 sx

shale	455
sand	500
shale & sand	850
red bed & shale	1214
anhydrite	1248
shale & shells	1800
lime & shale	3495
sand & shale	3520
lime 3554 RTD=3552 SIM	3556
Total Depth	3556

TOPS(CORR.):

Heebner	3177
Dodge	3200
Lansing	3229
Simpson	3485
Arbuckle	3518
Penetration	38

85 gals. oil in 1 hr.
94' oil in 1 hr.
213' oil in 3 hrs.
344' oil in 7 hrs.
425' oil in 9 hrs.
509' oil in 11 hrs.

Handwritten note: 2-2-54