

CITIES SERVICE OIL CO.
McCord No. 9

SEC. 26 T. 11 R. 17W.
NW NE SE
330' S. 990' W of E $\frac{1}{4}$ cor.

Total Depth. 3612
Comm. 4-13-41 Comp. 5-4-41
Shot or Treated.
Contractor. Maboo Oil and Gas Co.
Issued. 6-28-41

County Ellis.



CASING.

85/8" 1105' cemented.
5 $\frac{1}{2}$ " 3589' cemented.

Elevation.

Production. Pot. 3048 B.
no wtr. Echometer.

Figures Indicate Bottom of Formations.

| | |
|-------------------------|------|
| rock | 100 |
| shale | 235 |
| shale and shells | 865 |
| sand | 945 |
| shale and shells | 975 |
| shale and red bed | 1075 |
| red bed and shale blue | 1105 |
| shale and red bed | 1290 |
| anhydrite | 1340 |
| red bed | 1347 |
| shale and red bed | 1595 |
| salt and shale | 1707 |
| shale and shells | 1880 |
| lime broken | 2282 |
| lime and shale | 2756 |
| shale and shells | 2881 |
| lime and shale | 3018 |
| lime | 3257 |
| lime broken | 3396 |
| 3396 equals 3400 SLM | |
| lime broken | 3581 |
| 3581 Rotary T.D. equals | |
| 3590 S.L.M. | |
| dolomite | 3612 |
| Total Depth. | |

Corr. Top Arbuckle 3589
Penetration 23'

FILLUP - 175' oil in 1 hour
640' oil in 3 hours
340' oil in 4 hours
1300' oil in 6 $\frac{1}{4}$ hours
2000' oil in 9 hours
2600' oil in 15 hours

500 gal 5-5-41 1500 gal 5-6-41