

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bk Bldg, Wichita, Kansas.

Plotted JS.

CITIES SERVICE OIL CO.
McCord No. 10

SEC 26 T. 11 R. 17W.
SE NE SE
940' S & 330' W of E $\frac{1}{4}$ cor.

Total Depth. 3605
Comm. 5-31-41 Comp. 7-3-41
Shot or Treated.
Contractor, Mabee oil and gas Co.
Issued. 8-23-41

County Ellis.



CASING.

12 $\frac{1}{2}$ " 66' cemented.
8 $\frac{5}{8}$ " 360' cemented.
5 $\frac{1}{2}$ " 3553' cemented.

Elevation.

Production. Pot. 2850 B.

Figures Indicate Bottom of Formations, no wtr Echometer.

surface rock	55
shale	68
shale and shells	365
shale and red bed	625
sand and shale	720
shale and red bed	767
shale and shells	830
sand	905
shale shells and red bed	1255
anhydrite	1315
shale and shells	1377
red bed, shale and shells	1609
shale and salt	1735
shale and shells	2011
broken lime	2277
chert and lime	2280
broken lime	2302
lime and shale	2618
shale	2835
shale and lime	2988
lime	3130
lime broken	3205
lime	3232
lime broken	3299
lime	3330
3330 equals 3335 SLM	
lime	3536
lime and shale	3547
Arbuckle	3550
3550 Rot T.D. equals 3555 SLM	
dolomite	3598
lime	3605
Total Depth.	

Corr. Top Arbuckle 3552
Penetration 53'

FILLUP 150' oil in 1 hour.
250' oil in 1 $\frac{1}{4}$ hours.
1050' oil in 3 hours.
1500' oil in 4 hours.
2650' oil in 9 hours.

July 1, 1941. Echometer Potential
1040 oil, no water, 24 hours at
T.D. 3577
Deepened to 3605.

500 Gal. June 29, 1941
1500 gal. June 30, 1941
2000 gal. July 5, 1941