

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY

508 EAST MURDOCK - WICHITA, KANSAS

COMPANY CITIES SERVICE OIL CO.

SEC. 26 T. 11 R. 17W

FARM McCord

NO. 15

LOC. SW NE NE

915' S & 990' W of NEC

TOTAL DEPTH 3650 P.B. 3644

COUNTY Ellis

COMM. 11-7-50


COMP. 11-18-50

KANSAS

SHOT OR TREATED

CONTRACTOR Holm Drilling Co.

ISSUED 3-31-51



CASING

8 5/8" 316' cem. w/200 sx
5 1/2" 3650' cem. w/150 sx

ELEVATION 2087

Phy. Pot.
PRODUCTION 44 BO & 72% wtr

FIGURES INDICATE BOTTOM OF FORMATIONS

lime	75
shale & shells	316
shale	375
shale & shells	500
shale, shells & sand	900
sand, shale & shells	965
red bed	1265
anhydrite	1302
shale & shells	1685
salt, shale & shells	1800
shale & shells	2095
lime & shale	2285
shale & lime	2355
lime & shale	2555
shale & lime	2630
shale & shells	2950
shale & lime	3010
lime	3650 RTD

3650 RTD = 3650 SIM

Total Depth

Tops:

Lansing	3287
Simpson Shale	3548
Eros. Arbuckle	3557
Arbuckle	3560

Drilled cement to 3644' SIM.

Perf. 22 shots 3613-19

130' oil, trace wtr, 13-1/2 hrs.

Penetration 90'