

26-11-17W
State Geological Survey
 WICHITA BRANCH

W E L L L O G

OPERATOR: Cities Service Company

WELL NAME: McCord "A" # 18 LOCATION: 26-11s-17W NE SE SE

COUNTY: Ellis STATE: Kansas

WELL COMMENCED: April 28, 1981 WELL COMPLETED: May 6, 1981

ELEVATION: 2106' K.B. TOTAL DEPTH: 3664'

PRODUCTION: Oil RIG NO: #1

CASING - 8 5/8": 325.73' new 24# cemented with 250 sxs common 50-50 poz did not circulate

5 1/2": 14# 3664' Set 2' off Bottom @ 3662' cemented with -1st stage 20bbl. salt water 250 sxs 50/50 poz "A" 10% salt .75% CFR2 -2nd stage 250 sxs Howco Lite

ALL MEASUREMENTS TAKEN FROM THE TOP OF ROTARY BUSHING: 10% .75% CFR2 P.D. @ 8: 00 A.M.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0'	328'			
328'	532'	sand and shale		
532'	1264'	sand and shale	1264' - 1 - degree	
1258'	1264'	Anhydrite		
1264'	1294'	Anhydrite		
1294'	1491'	shale and lime		
1491'	1952'	shale and lime		
1952'	2173'	shale and lime		
2173'	2366'	shale and lime		
2366'	2559'	shale and lime		
2559'	2695'	shale and lime		
2695'	2895'	lime and shale		
2895'	3058'	lime and shale		
3058'	3177'	lime and shale		
3177'	3297'	lime and shale		
3297'	3401'	lime and shale		
3401'	3481'	lime and shale		
3481'	3555'	lime and shale	3555' - 1 - degree	
3555'	3575'	Arbuckle		
3575'	3600'	Arbuckle		
3600'	3634'	Arbuckle		
3634'	3664'	Arbuckle		
3664'	RTD			

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 21 1981
 CONSERVATION DIVISION
 Wichita, Kansas