


Plotted Texas CO *Wichita*

DEEPROCK OIL CO.
Baumer No. 1.

SEC. 27 T. 11 R. 17W
NW NW NW
330' fr NL 330' fr WL

Total Depth. 3451½
Comm. 2-27-37 Comp. 3-30-37
Shot or Treated.
Contractor. Helmerich & Payne Inc.
Issued. 6-19-37

County. Ellis



CASING:
15½ 118'
10 1196'
6 5/8 3444'

JUN 19 1937

Elevation.

Production. Pot. 3055 B.

Figures Indicate Bottom of Formations.

shale blue	80	shale red & blue	2490
shells hrd	85	lime hrd	2505
shale blue	185	shale	2560
sticky shale, iron	345	lime	2570
shale blue	425	shale - lime	2580
sand	445	shale	2645
shale	500	shale blue	2710
shale blue	560	lime	2730
sand	610	shale	2760
shale blue	635	lime	2790
red rock sand	640	shale	2810
shale & shells	800	shale & shells	2860
sand & sdy shale	840	shale	2880
shale & shells	910	lime - shale	2890
shale blue	930	shale	2905
shale red & shells	1015	shale & shells	2930
shale & shells	1040	lime	2945
red rock, sdy shale	1070	shale	2975
shale red bed anhydrite	1175	lime	3000
1150-60		Topeka lime	3025
anhydrite	1189	lime	3040
anhydrite hrd	1197	lime grey	3090
anhydrite	1260	sdylime sft	3097
sticky red bed	1275	lime	3148
iron, red bed, shale	1295	lime & shale	3170
red bed & shale	1425	lime	3210
red rock & shale	1510	lime (very hrd 3211-14)	3245
lime	1520	shale blue-green-red	3260
shale	1525	lime white-grey	3270
red bed-shale	1560	shale blue-brown	3275
salt, shale	1570	lime brown	3285
salt	1600	lime	3305
slate shells	1645	lime white hrd	3330
shale	1775	lime	3335
brkn lime	1835	brkn lime-shale	3355
shale	1845	lime hrd	3365
lime hrd	1925	brkn lime	3370
lime brkn hrd	1940	lime	3400
lime	1990	lime brkn & shale	3430
shale red	2000	Simpson lime sh oil	3440
shale lime	2020	Simpson dolomite sat.	3442
lime	2045	Siliceous lime &	
brkn lime	2090	dolomite	3444
shale	2105	Siliceous lime-pay	3451½
lime	2120	Total Depth.	
shale	2125		
lime	2185		
lime hrd	2210		
lime	2275		
lime white	2310		
shale red	2320		
lime white	2330		
lime	2335		
shale red	2365		
lime	2470		
lime M.H.	2480		

Log information as correlated from samples:

Drilling record from rotary samples 1890-3443

Drilling record from core 3443-3447½

Drilling record from cable tool samples 3447-3451½

Top Anhydrite 1189

Top Topeka lime 2975

Show oil Topeka 3090-98

Show oil Topeka 3215-20

Top Kansas City-3260

Lansing

Show oil 3315-3325

Show oil 3360-3370

Show oil 3400-3415

Simpson lime good show oil 3433-3440

Record of Pay Sand

Cherty Siliceous lime 3444-47

300' oil in hole

Dolomite brown 3447-49

1600' oil in hole

Coarse dolomite 3449-50

2800' oil in hole

Siliceous lime 3450-51'6"

3200' oil in hole.