

DEEP ROCK OIL CORP.
Baumer No. 3

SEC. 27 T. 11 R. 17W.

~~NW SW NW~~


SW NW NW

County Ellis.

Total Depth. 3419
Comm. 4-17-37 Comp. 5-13-37
Shot or Treated.
Contractor.
Issued. 6-26-37

CASING.

JUN 26 1937



15 $\frac{1}{2}$ " 56'
12 $\frac{1}{2}$ " 1160'
65 $\frac{1}{8}$ " 3413'

Elevation.

Production. Pot. 2943 B.

Figures Indicate Bottom of Formations.

clay and shale	54
shale	170
shale	325
shale and sand	500
sand	640
shale	702
shale streaks iron & lime	864
shale and sand	1060
red bed and shale	1145
chalk lime and anhydrite	1162
anhydrite	1210
red bed	1340
red bed and red rock	1550
red bed	1725
broken lime	1775
lime	1895
red rock lime & grey shale	1955
lime	2005
lime and red rock	2075
lime shale and red rock	2186
lime streaks of shale	2238
shale	2248
lime and red rock	2340
lime and shale	2400
lime and shale streaks	2415
shale	2490
lime and shale	2535
broken lime	2550
shale	2600
shale and lime	2625
shale	2665
shale streaks of lime	2730
shale and lime	2774
shale	2825
shale and shells	2870
shale and lime	2900
lime	2935
lime chert	2995
lime	3412
siliceous lime Pay	3419

Total Depth.