


*Plotted
Albert H. H. H.*

DEEP ROCK OIL CO.
Baumer No. 7.

SEC. 27 T. 11 R. 17W
SW SW NW
2310' fr NL 330' fr WL

Total Depth. 3542'
Comm. 6-9-37 Comp. 7-6-37
Shot or Treated.
Contractor. Helmerich & Payne, Inc.
Issued. 8-14-37

County. Ellis



AUG 14 1937

CASING:
15 1/2" 53'
10 " 1250'
7 " 3531'

Elevation.

Production. Pot. 2323 B.

Figures Indicate Bottom of Formations.

shale	42
shale, shells & anhydrite	1250
anhydrite	1280
shale, red beds & shells	1655
shale	1780
lime brown	1900
shale & sdy lime	2020
shale	2030
lime	2080
lime & shale	2285
lime	2375
red bed & lime shells	2425
lime	2500
shale	2515
shale & shells	2720
shale	2835
brkn lime	2995
shale	3002
lime	3465
lime & shale	3515
lime	3542
Total Depth.	

Summary	
Anhydrite (Cimmaron)	1245
Neva Ls.	2425
Tarkio Ls.	2780
Topeka Ls.	3000
Show oil saturation in samples	3130-50
" " " " "	3250-75
" " " " "	3300-10
Lansing-Kansas City	3320
Show oil saturation in samples	3320-50
" " " " "	3410-90
Simpson	3505
Simpson Sand-Sh oil sat. in samples (Core)	3526
Siliceous lime - oil (Cored 6' of Siliceous Ls)	3532
Total Depth (Drld 6' of Sil.Ls.)	3542