


DEEP ROCK OIL CORP.
Baumer No. 19

SEC. 27 T. 11 R. 17W
NE SE NW
1650' fr NL 2310' fr WL

Total Depth. 3542'
Comm. 8-19-37 Comp. 9-14-37
Shot or Treated.
Contractor.
Issued. 2-26-38

County. Ellis

FEB 26 1938



CASING:

16 "	38'
10 ³ / ₄ "	1291'
7 "	3528'

Elevation.

Production. Pot. 3370 B.

Figures Indicate Bottom of Formations.

surface clay	38
shale & shells	490
sand & shale	625
sand, shale & shells	1020
shale & iron	1265
shale & red rock	1286
anhydrite	1320
red bed	1450
red bed, shale & sand	1710
shale	1820
brkn lime	2035
shale & shells	2150
brkn lime	2230
shale & lime shells	2320
lime	2400
shale	2430
lime	2455
shale & lime shells	2505
shale, strk salt	2545
shale & lime shells	2625
lime	2650
shale	2790
shale & lime shells	2910
shale	2990
lime & chert	3020
lime shale breaks	3060
shale & chert	3077
lime	3205
lime shale breaks	3245
lime	3344
brkn lime & shale	3360
lime	3528
Siliceous lime Pay	3542
Total Depth.	