


DEEP ROCK OIL CORP.
Baumer No. 23

SEC. 27 T. 11 R. 17W
SE NE NE
990'fr NL 330'fr EL

Total Depth. 3396'
Comm. 9-27-37 Comp. 10-18-37
Shot or Treated.
Contractor.
Issued. 3-12-38

County. Ellis

MAR 1 2 1938



CASING:

16 "	41'
10 ³ / ₄ "	1131'
7 "	3382'

Elevation.

Production. Pot. 3234 B.

Figures Indicate Bottom of Formations.

cellar	9
surface clay	41
shale & shells	310
sand	440
shale & shells	540
sand	560
shale & shells	690
sand	770
s hale & shells	830
shale	900
red bed & shells	1122
anhydrite	1131
anhydrite	1152
red bed	1225
shale & shells	1480
salt	1670
shale & shells	1946
shale & lime	2040
brkn lime & shale	2169
shale & lime	2280
red rock	2300
lime & shale	2325
lime	2381
shale & shells	2420
lime	2480
shale	2532
lime	2540
shale	2627
shale & shells	2690
lime	2710
shale & shells	2761
shale & lime	2830
lime Topeka	3090
lime Kansas City	3376
lime & shale	3381
lime Siliceous	3392
cherty lime	3396
Total Depth.	