

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bk Bldg., Wichita, Kansas.


DEEP ROCK OIL CORP.
Baumer No. 24.

SEC. 27 T. 11 R. 17W
NE SW NE

Total Depth. 4002' P.B. 3496'
Comm. 10-6-37 Comp. 11-5-37
Shot or Treated.
Contractor.
Issued. 3-26-38

MAR 28 1938

County. Ellis



CASING:
16 " 28'
103/4" 1225'
7 " 3521'

Elevation.

Production. Abnd.

Figures Indicate Bottom of Formations.

surface clay	22	sdv lime	3747
shale blue	165	sdv lime & shale break	3780
shale & shells	620	lime & iron pyrite	3794 ✓
sand	650	lime	3829
shale & shells	740	sand	3833
sand	830	sdv lime	3900
shale	950	lime	4002
red rock-shale & strks sand	1200	Total Depth.	

lime brown 1208

gypsum 1219

anhydrite 1266

shale & shells 2110

shale & lime 2180

lime shells 2240

lime 2272

lime & red rock brks 2307

lime shells 2365

shale red 2380

lime brkn 2450

brkn lime & red rock 2510

lime 2555

shale & strks lime 2640

shale & shells 2785

brkn lime & shale 2920

brkn lime 2964

shale & shells 2985

lime 3020

lime white 3055

sdv lime 3075

lime hrd 3095

brkn lime 3120

lime 3187

brkn lime 3230

shale & shells 3295

lime 3340

lime white hrd 3365

lime 3455

shale 3460

lime 3473

shale red & conglomerate 3741

Plugged back 3496

Note: Hole drilled to 4002' and dry
Pipe run and cemented at 3521 and
left standing for future tests in
upper sands. Plug has not been drilled
after pipe was cemented. Top plug
3496'