


DEEP ROCK OIL CORP.
C. A. Baumer No. 28.

SEC. 27 T. 11 R. 17W
NEc SE
330' NL 330' EL

343 28 1939

Total Depth. 3409'
Comm. 2-7-38 Comp. 3-1-38
Shot or Treated.
Contractor. Helmerich & Payne
Issued. 1-28-39 Rotary

County. Ellis



CASING:

16 " 79'
10³/₄" 1146'
7 " 3394'

Elevation.

Production. Pot. 3339 B.
No water

Figures Indicate Bottom of Formations,

shale & sand	79
shale & shells	485
shale & sand	650
shale & shells	715
sand	810
shale & pyrite	1015
red rock	1120
shale & red rock	1141
gyp	1143
anhydrite	1150
1150 equals 1146 SLM	
anhydrite	1185
shale & shells	1210
red rock	1285
shale & shells	1710
lime	1850
brkn lime	1920
lime	2070
brkn lime	2105
shale & shells	2140
lime brkn	2375
shale & shells	2395
lime	2405
shale	2435
brkn lime	2465
lime	2495
shale & shells	2585
shale	2645
shale & shells	2845
lime	3100
shale & lime	3150
lime	3394
Core 3394-98 Rec 2.6'	
dolomite Rust	3398
Top Arbuckle Dolomite 3393 Corr.	
dolomite	3409
Total Depth.	

2700' oil 1 hour
Increase to 2900' oil

Est. State Potential rating of 3339 B. and no wtr
in 24 hours. based on lowest 4 hours of 8 hour test
3-6-38 pumping.