

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas


Plotted H.C.W.

DEEP ROCK OIL CORP.
Baumer No. 36

SEC 27 T. 11 R. 17 W.
CW $\frac{1}{2}$ SW SE

Total Depth. 3593
Comm. 11-28-41 Comp. 12-27-41
Shot or Treated.
Contractor.
Issued. 3-7-42

County Ellis



CASING.

13" 39' cemented.
85/8" 1318' cemented.
5 1/2" 3576' cemented.

Elevation.

Production. Pot. 2540 B.

Figures Indicate Bottom of Formations.

surface clay	39
surface rock & clay	136
shale blue	380
shale	520
red shale and sand	610
shale and sand	640
shale	720
sand strks and shale	805
sand and shale	1045
shale	1325
anhydrite	1347
red shale and shells	1525
shale lime shells	1700
shale and shells	1965
broken lime & shale	1995
lime	2030
shale and lime	2525
lime with thin strks of shale	2558
lime and small shale breaks	2615
lime hard and shale streaks	2635
shale and lime strks	2745
shale and lime shells	3005
lime and shale	3035
lime broken	3075
lime	3165
lime & shale brks	3180
lime	3285
lime and shale	3325
lime and shale strks	3410
lime	3438
lime & shale strks	3518
broken lime	3576
lime Arbuckle (Pay)	3593

Total Depth.