

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.


Plotted
J.R.

DEEP ROCK OIL CORPORATION.
Baumer No. 37

SEC. 27 T. 11 R. 17 W.
CE $\frac{1}{2}$ SE SW

Total Depth. 3585
Comm. 1-18-42 Comp. 2-17-42
Shot or Treated.
Contractor.
Issued. 4-18-42

County Ellis.



CASING.

12 $\frac{1}{2}$ " 33' cemented.
8 $\frac{5}{8}$ " 1320' cemented.
5 $\frac{1}{2}$ " 3571' cemented.

Elevation.

Production. Pot. 157,000 B.
drawdown.

Figures Indicate Bottom of Formations.

caliche	60
shale	435
sand	450
shale and shells	580
sand	600
shale and shells	700
lime and shale	1100
shale	1230
broken shale and lime	1318
anhydrite	1348
shale and shells	1650
shale	1850
broken shale and shells and lime	1930
lime	2115
lime with shale breaks	2210
lime	2395
shale and lime	2465
lime	2530
broken lime	2635
shale and lime	2745
shale and lime shells	2875
lime and shale	2925
shale	2960
lime	2975
shale	3012
broken lime	3030
lime	3255
shale	3285
broken lime	3360
lime	3516
lime and shale	3570
lime Arbuckle Pay	3585
Total Depth.	

157,000 B. drawdown potential.
56.4 bbls Prorated.

cement down 64' back of 8" casing.
Ran 1" pipe to top of cement and
filled hole with 28 sacks of cement