


DEEP ROCK OIL CORPORATION.
Baumer No. 38

SEC. 27 T. 11 R. 17 W.
CEL SW SW
990' f WL 660' f SL SW $\frac{1}{4}$

Total Depth. 3637
Comm. 2-20-42 Comp. 3-18-42
Shot or Treated.
Contractor.
Issued. 5-16-42

County Ellis.



CASING.

13" 45' cemented.
8 $\frac{5}{8}$ " 1350' cemented.
5 $\frac{1}{2}$ " 3633' cemented.

Elevation.

Production. Pot. 100 B.

Figures Indicate Bottom of Formations.

lime	45
shale	350
sand	380
shale and shells	430
shale	465
salt	540
shale	600
shale and shells	670
sand	780
shale and lime shells	860
shale	900
sand	975
broken lime	1040
shale red bed and shells	1190
red bed and shale	1305
anhydrite	1360
red bed	1560
shale salt and shells	1735
shale and shells	1950
broken lime	2000
shale and lime	2175
broken lime	2300
lime	2420
broken lime	2480
shale and lime	2500
broken lime	2605
shale and lime	2655
lime and shale strks	2700
lime and shale	2765
shale and shells	2880
lime and shale	3045
lime	3110
lime hard	3140
lime	3265
cherty lime	3280
shale	3305
lime	3488
lime and shale	3525
lime	3555
lime and shale	3572
lime	3633
Arbuckle lime Pay	3637

Total Depth.