

Plotted Texas *Co. but Shells*

THE TEXAS CO.
F.A. Bemis No. 3A.


SEC. 28 T. 11 R. 17W
NW NE NE
330' fr N 990' fr EL NE $\frac{1}{2}$

Total Depth. 3382'
Comm. 5-3-37 Comp. 6-9-37
Shot or Treated.
Contractor. Helmerick & Payne, Inc.
Issued. 7-24-37 Rotary 0-3366
Cable 3366-3382

County. Ellis

CASING:
15 $\frac{1}{2}$ " 57'
10 $\frac{3}{4}$ " 1093'
7" 3365'

JUL 24 1937



Elevation.

Production. Pot. 2095 B.

Figures Indicate Bottom of Formations.

shale	50	K.C. lime	2898
lime	62	lime	3000
shale	88	shale	3019
shale & shells blue	236	lime	3100
shale & shells	415	shale	3125
lime & shells	480	lime	3150
sand & lime	500	lime & shale	3198
shale	610	lime	3222
shale & shells blue	675	lime hrd	3244
wtr sand	710	lime	3355
shale blue	796	Simpson shale	3360
red rock	905	shale green	3363
shale	990	sand, shale	3364
lime	1040	dolomite	3366
shale	1073	Siliceous lime	3382
lime	1093	Total Depth.	
lime	1134		
red bed	1210		
shale	1370		
sand	1395		
lime & shale	1480		
salt & shale	1518		
shale & shells	1760		
lime & shale	1823		
lime	1940		
shale	1961		
lime hrd	2010		
lime	2100		
lime hrd	2130		
lime	2175		
chalk	2200		
brkn lime	2260		
red rock	2276		
lime	2298		
shale	2305		
lime	2353		
shale & shells	2412		
lime & shale	2443		
lime	2482		
shale & brkn lime	2500		
lime	2552		
shale	2567		
shale & shells	2635		
lime	2650		
shale	2683		
shale & shells	2736		
brkn lime	2760		
shale & shells	2798		
shale	2840		
lime hrd	2865		
shale & lime	2886		