

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.  
412 Union National Bank Bldg, Wichita, Kansas.

PLOTTED  
G.E. Jameson


TEXAS COMPANY.  
F.A. Bemis No. 7-A.

SEC. 28 T. 11 R. 17W.  
NE NW NE  
330' fr W & 990' fr NL NE  $\frac{1}{4}$

Total Depth. 3391  
Comm. 7-2-37 Comp. 8-11-37  
Shot or Treated.  
Contractor. J.E. Trigg.  
Issued. 9-11-37

SEP 11 1937

County. Ellis.



CASING.

0 to 32'  
Rotary 32 to 3381  
Cable 3381 to 3391

16" 32'  
10 3/4" 1100'  
7" 3381'

Elevation.

Production. Pot. 2032 B.

Figures Indicate Bottom of Formations.

surface	32
shale	160
shale and shells	508
shy shale	793
shale and shells	945
red bed	1094
lime	1145
red bed	1318
shale and shells	1418
salt	1700
shale and shells	1965
lime	2075
shale and shells	2343
lime	2487
shale	2560
shale and shells	2678
lime	2705
shale	2860
limo	3330
shells and green shale	3377
Simpson sand	3380
lime	3391

Total Depth.

Not acidized.