

G. E. Jameson

TEXAS COMPANY.
 F.A. Bomis No. 10-A

SEC. 28 T. 11 R. 17W.
 SW NE NE
 990' fr N & E L. NE $\frac{1}{4}$


Plotted Texas CO.

County Ellis.

Total Depth. 3482
 Som. 8-14-37 Comp. 9-16-37
 Shot or Treated.
 Contractor. J.E. Trigg.
 Issued. 10-2-37

OCT 2 1937

CASING. Rotary 3473
 Cable 3482



16" 30'
 10 3/4" 1200'
 7" 3473'

Elevation.

Production. Pot. 2307 B.

Figures Indicate Bottom of Formations.

surface	30
shale and sholls	600
sand	670
shale and sholls	735
sand	850
shale	1200
limo	1240
shale and sholls	1550
salt	1815
shale and sholls	1900
limo	1977
shale and sholls	2095
limo	2256
shale and sholls	2453
shale	2510
limo	2574
shale	2730
lime	2740
shale	2765
lime	2770
shale and sholls	2809
lime	2835
shale and sholls	2860
shale	2907
shale and sholls	2969
lime	3454
shale groon	3465
sand	3472
limo	3482

Total Depth.

Not acidized.